

4-041393

7-30

15-063-01753-00-00

13  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 2-15-48

SE SE NE /4 SEC. 27, 09 S, 20 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 3456

Lease Rathbun well # 5 <sup>KCC TAP</sup>

Operator: A.F.G. Energy, Inc.

County Rooks

Address: P.O. Box 605  
Russell, Kansas 67665

Well total depth 3852 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 131 feet

125.19

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:30A.M. Day: 30 Month: July Year: 92

Plugging proposal received from: Terry Piesker

Company: A.F.G. Energy, Inc. Phone: 913-483-6213

Were: 5 1/2" casing set @ 3804' w/150 sx. cement. Perf. @ 3589'.  
Anhy. Perf. @ 1770'. Squeezed @ 62' with 25 sx. 113' w/125 sx.  
Re-squeezed with 75 additional sx. Ordered 300 sx. 60/40 pozmix -  
10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 6:30P.M., Day: 30, Month: July, Year: 92

Actual plugging report: M.I.R.U. Ran in hole with tubing to 3400'.  
(tagged top of sand) Spot 150 sx. cement with 300# hulls. Pulled  
tubing to 1500'. Spot 50 sx. cement with 100 # hulls to circulate  
at surface. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing.  
Squeezed 100 sx. cement with 100# hulls. Max. 1000#. S.I. 800#.  
Annular space filled with cement from previous squeeze.

RECEIVED  
STATE CORPORATION COMMISSION  
8/12/92  
AUG 12 1992

Remarks: Top of fluid NA  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  , CASING  . Elevation: GL

CONSERVATION DIVISION

I did  / did not  observe the plugging.

Dennis L. Hamel

DATE 8-20-92  
INV. NO. 35989

(agent)