

10-22 4-070073

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,213-00-00

SW NE SE /4 SEC. 08, 09 S, 19 W
1650 feet from S section line
990 feet from E section line

Operator license# 30742

Lease: McClellan Well # 3

Operator: Palomino Petroleum, Inc.

County: Rooks 114.86

Address: 4924 SE 84th Street
Newton, Kansas 67114-8827

Well total depth 3534 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 206 feet
W/150 sxs.

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Palomino Petroleum, Inc. License# 30742

Address: 4924 SE 84th Street - Newton, Kansas 67114-8827

Company to plug at: Hour: 8:00 A.M. Day: 22 Month: October Year: 1997

Plugging proposal received from: Klee Watchous

Company: Palomino Petroleum, Inc. Phone: 316-799-1000

Were: Ordered 275 sxs 60/40 pozmix - 10% gel with 800# hulls.
5 1/2" set at 3532' w/150 sxs. PBTB 2900' cast iron plug. KC perms 3396' - 3416'.
Run tubing to 2700' - circulate cement to surface. Pump 50 sxs w/200# hulls down annulus.
Elev. 2049' GL - Anhy. 1470' - Salt 1885'.

10-29-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 1:00 P.M., Day: 22, Month: October, Year: 1997

Actual plugging report: Ran tubing to 2700'. Halliburton pumped 80 sxs Mid Con II with 350# hulls. Pulled to 1400' - pumped 70 sxs with 350# hulls. Circulated cement. PTOH Squeezed 10 sxs. Max. P.S.I. 500#. S.I.P. 300#. Pumped 40 sxs with 100# hulls down annulus. Max. P.S.I. 500#. S.I.P. 400#.

Remarks:

Condition of casing(in hole): GOOD _____ BAD Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2049 GL

I did / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE OCT 30 1997

INV. NO. 49403