

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20222-00-00
Spot: CSWSWSE. Sec/Twnshp/Rge: 8-9S-19W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MCCLELLAN Well Number: 5
County: ROOKS Total Vertical Depth: 3525 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet: 8 1/4.56
Surface Casing: Size 8.625 feet: 205 w/150 sxs cmt
Production: Size 5.5 feet: 3522 w150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/20/2002 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 800# hulls.
No squeezed records. Perforate Salt 1915' - Anhy at 1490' - Dakota 815'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/20/2002 3:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 3200'.
No pipe recovery.
Perforated: Salt at 1915' - Anhy at 1490' - Dakota at 815'.
Ran tubing to 2500'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 1000'. Allied pumped 120 sxs cement with 300# hulls - cement circulated.
PTOH. Squeezed with 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside. Pumped 50 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
JAN 03 2003
1-3-03
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 1-3-03
INV. NO. 2003061023

DEC 30 2002

KATHOL PETROLEUM, INC. #5 MC CLELLAN 8-9-19W
 WICHITA, KS. SW SW SE
 Contr. CO. TOOLS Cty. ROOKS
 Geol. Pool MC CLELLAN
 E. 2051 KB Cm. 6/17/69 Cp. 8/7/69 IP PMP 140 BOPD, NW/
 LANS 3390-3430, GR
 API 15-163-20,222 37

SMP Tops	Depth	Datum
ANH	1459	+ 592
B ANH	1498	+ 553
HEEB	3217	-1166
TOR	3236	-1185
LANS	3256	-1205
BKC	3459	-1408
CONG	3501	-1450
ARB	3513	-1462
TD	3525	-1474

Csg. 8-5/8" 205/150 SX
 5 1/2" 3522/150 SX
 DST 3382-3420/45", 75' GIP, 120'
 SO&GCM, 205' FROGGY OIL,
 120' OIL, BHP 272-272#/30"
 FP 72-228#, TEMP 98
 PF 3426-30, 500 MA, 1500 REG ACID
 SWB LD & SWB 6 BOPH, PF 3409-13,
 SET PLUG 3418, 1500 ACID, SWB LD
 & SWB 8 1/2 BOPH, SWB 18 BOPH, PF
 3390-93, 1500 ACID, SWB LD & SWB
 32 BOPH, ALL ZONES, POP, PMP 140
 BO, NW
 NO LOG
 NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS