

15-163-01588-00-00

6 010739

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Jan 1., 1990
C SW SE, SEC. 32, T 9 S, R 18 W/E^{xx}

TECHNICIAN'S PLUGGING REPORT

Operator License # 5252

660 feet from S section line

1980 feet from E section line

Operator: R. P. Nixon Oper Inc.

Lease Name Richardson Well # 2

Name & Address 207 W. 12th Street

County Rooks 120.41

Hays, Ks. 67601

Well Total Depth 3705 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well xx Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor R. P. Nixon License Number 5252

Address Same

Company to plug at: Hour: PM Day: 13 Month: Dec. Year: 19 90

Plugging proposal received from Dan Nixon

(company name) Same (phone) _____

were: Order 350 sks cement 65/35 poz 8% gel 500 lbs. hulls. 5 1/2 casing at 3699.

Holes in pipe 840 to 1410. Sq w/150 sks cement. Baker R. 4 retrieveable. Lock

set plug stuck at 3110 pulled 60,000 lbs. Would not come. Unseated and pulled one joint.

Plugging Proposal Received by D. F.B.

(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 13 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Pumped down 8 5/8 100 sks cement w/300 lbs. hulls. Max pres.

400 lbs. Closed w/200 lbs. Pumped down tubing 125 sks cement w/100 lbs. hulls. Pulled

1500 of tubing. Pumped down 90 sks cement w/200lbs. hulls circulated, pulled tubing,
tied onto casing. Pumped down 25 sks cement. Max pres 800 lbs. closed

RECEIVED
STATE CORPORATION COMMISSION

12/18/90
DEC 18 1990

Remarks: Allied Cement Co. (Gary)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(If additional description is necessary, use BACK of this form.)
(If not observed, observe this plugging.)

DATE JAN 09 1991

INV. NO. 30442

12-13

Jub

Signed Walter Balthazor
(TECHNICIAN) Balthazor