

4-042049

05-15-78

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,776 -00-00

C NW SE /4 SEC. 34, 09 S, 18 W
1980 feet from S section line
~~1980~~ 2080 KCC feet from E Section line
ZAP

Operator license# 4525
Operator: A. Francis Vonfeldt Co. 5/4
Address: 505 S. Colorado
Plainville, Kansas 67663

Lease: Collins Well # 2
County: Rooks 119.86
Well total depth ~~3688~~ 3690 KCC ZAP feet
Conductor Pipe: inch @ feet
Surface Pipe: 8 5/8 Inch 216 Feet
W/170 sxs/

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services License# -

Address: Ness City, Kansas 67560

Company to plug at: Hour: 8:00 A.M. Day: 4 Month: May Year 2000

Plugging proposal received from: Francis Vonfeldt

Company: A. Francis Vonfeldt Company Phone: -

Were: Ordered 150 sxs Swift Lite with 10 sxs gel plus 300# hulls.
5 1/2" casing set at 3689' w/150 sxs cement. Perf at 3374' - 3641'.
D.V. anhy. At 1480' w/450 sxs. Tubing fish at 2328'.

RECEIVED
STATE CORPORATION COMMISSION
5/19/00
MAY 9 2000

Plugging Proposal Received by: Dennis Hamel CONSERVATION DIVISION
Plugging operations attended by agent? All , Part , None Wichita, Kansas

Completed: Hour: 12:00 P.M., Day 4, Month: May, Year: 2000

Actual plugging report: Shot tubing off at 2328'. Pulled 2 joints. RU cementers and spotted 20 sxs cement (9 bbls) or (400 sxs) of cement at 2265' plus 200# hulls. Pulled dto 1865' and spotted 600' of gel. Pulled to 1400' and spotted 60 sxs cement with 200# hulls. Cement did not circulate. Pulled tubing and shut down for cement.
05-50-2000 - Ran WLM T.O.C. at 500'. R.I.H. with tubing to 485'. Spotted 40 sxs cement to circulated cement at surface. Job complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING CASING . Elevation: G.L.

I did / did not observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE 5/10/00
INV. NO. 61709

Form CP-2/3

(R)