

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20189-00-01
Spot: NW NW SW Sec/Twnshp/Rge: 9-9S-19W
2490 feet from S Section Line, 4800 feet from E Section Line
Lease/Unit Name: MCCLELLAN Well Number: 2
County: ROOKS Total Vertical Depth: 3541 feet

Operator License No.: 6622
Operator Name: JASON OIL COMPANY
Address: PO BOX 701
RUSSELL, KS 67665

Conductor Pipe: Size
Surface Casing: Size 8.62
Production: Size 5.5
Liner: Size

feet:
feet: 199
feet: 3539
feet: 115.05

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/18/00
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2476

Proposed Order 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Plugging Order sand and common cement.
Method:

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/18/2000 2:15 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 199' w/175 sxs. 5 1/2" set at 3539' w/150 sxs.
Prod perfs 3250' - 3455'. Sanded back to 3200' w/5 sxs common cement on sand with bailer. Recovered 1026' of 5 1/2" casing with shot 1590'.
Squeezed w/200 sxs cement blend with 400# hulls mixed in to Max. P.S.I. 600#. Plug complete,

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION SHOULD READ AS FOLLOWS: 150' E. OF NWNWSW.

Plugged through:

District: 04

Signed

Carl Goodrow Part II

(TECHNICIAN)

INVOICED

DATE

10/4/00

INV. NO.

2001060790

SEP 21 2000

Form CP-2/3

ENERGY RESERVES GROUP

#2 MCCELLAN 'OWMO'

9-9-19W
1501E
C NW NW SW

BOX 1201
WICHITA, KS 67201

CONTR UNKNOWN

GEOLOGICAL

CTY ROOKS
FIELD MCCELLAN

ELV 2063 Kbps 11/1/82 CARD ISSUED 1/20/83 IP P 3 BO & 70 BWPD

LKC 'D' 3331-3333

-	-	-
-	+	-
-	+	-
-	+	-
-	+	-
-	+	-

API 15-163-20, 189-A

OLD INFO: OPERATOR WAS O. A. SUTTON, #2 MCCELLAN, SPD 3/14/69, SET 8 5/8 " 199175SX: 5 1/2 " 3538/150SX, COMPLETED AS P 94 BOPD, LKC 3418-3457, CONTR: GABBERT-JONES
DST (1) 3507-3541 (ARB) / 90", REC 20' M, W / FEW SPOTS OIL, SIP 73-63# / 45", FP 42-52#
MCT - CO, PF (PENN) 3455-57, AC 1250G, SWB 3 BOPH / 6 HRS, PB 3445, PF (LKC) 3434-36, AC 1250G, SWB 5 BOPH / 4 HRS, PB 3426, PF (LKC) 3418-20, AC 1250G, FU 2350, FIH / 12 HRS, SWB 6 BOPH / 3 HRS, BP 3410, PF (LKC) 3399-3401, AC 1250G, SWB 8 BOPH, CO PLUGS, SWB 15 BOPH / 4 HRS, POP
NEW INFO: RE-ENTERED 11/1/82, WSH DWN, MCT - CO, PF (LKC) 3331-33, SWB LD, R&T, POP, P 3 BO & 70 BWPD, 11/10/82

LOG	Tops	Depth/Datum
HEEB	3224-1161	
TOH	3248-1185	
LKC	3266-1203	
BKC	3465-1402	
ARB	3514-1451	
RTD	3541-1478	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS