

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23341-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 9-9S-19W
4520 feet from S Section Line, 1770 feet from E Section Line
Lease/Unit Name: HERONEME/HOGAN Well Number: 1-9
County: ROOKS Total Vertical Depth: 3545 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 243 **\$115.21**
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/22/2001 2:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/22/2001 6:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3450' w/25 sxs. Ar buckle 3470'.
2nd. Plug at 1475' w/25 sxs. Anhydrite 1456' - 1493'.
3rd. Plug at 800' w/100 sxs. Dakota 476' - 776'.
4th. Plug at 300' w/40 sxs. Surface pipe at 243'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

KANSAS CORPORATION COMMISSION
JAN 07 2002
1-7-02
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

KANSAS CORPORATION COMMISSION

(TECHNICIAN)

JAN 07 2002

CONSERVATION DIVISION

INVOICED

Form CP-2/3

DATE 01-08-02

INV. NO. 2002061214

JAN 03 2002