

6 041070

9-12 15-163-19301-00-01 ~~164~~ 164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-21,843
SW SE SE, SEC. 2, T 9 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line
990 feet from E section line

Operator License # 5229

Lease Name Barry SWS Well # D0 7

Operator: Phillips Pet Co.
Name & Address 510 NW 3rd
Plainville, Ks. 67663

County Rooks 120.32
Well Total Depth 3702 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 200' cwc

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. License Number _____

Address Hays, Ks.

Company to plug at: Hour: 10:00 AM Day: 12 Month: Sept Year: 19 89

Plugging proposal received from Dave Stahl

(company name) P. P. Co. (phone) _____

were: 7" casing at 3443' w/T.O.C. at 3100': 4 1/2" liner run to 3413' to surface

cwc to within 300' of surface. LKC and Dakota squeezed prior to running 4 1/2" liner: 2 7/8"

tubing. Workstring stuck in hole at 1605' to 571':

RECEIVED
STATE CORPORATION COMMISSION
10/2/89
OCT 2 1989

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:10PM Day: 12 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT MI Rig, cleaned out tubing to 1600' : rig up perforators,

perf tubing - casing at 1400' and 900': RIH w/1" tubing spot. 50 sks common cement on bottom;

pull up to 600' w/1" tubing, circ cmeent to surface, pull 1" tubing; 50 sks

60/40 poz 6% gle: Hooked up to 4 1/2" casing, sq add 300 sks 60/40 poz 6% gel: Max psi 300#

S.I. 150#: cement cir annulus. 4 1/2" casing hooked up 10 3/4" s.p. and sq 0 sks cement. Max

1400# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE 10-17-89 JLS

INV. NO. 26020

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel