

7-11

6 041192

11-12-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-02295-00-00

NE, SEC. 10, T 9 S, R 19 W/E

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916

Lease Name Dan Barry C Well # 3

Operator: Conoco Inc.

County Rooks 113.23

Name & Address 3817 Expressway

Well Total Depth 3484 feet

Okla City, OK. 73112

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 196 w/150 sks

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Services License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00AM Day: 11 Month: July Year: 19 90

Plugging proposal received from Dave Lorenzo

(company name) Conoco (phone)

were: 5 1/2 casing set at 3467 w/200 sks cement: perfs at 3132 to 38. Perf anhy at 1471; perf base dakota at 831.

Ordered 475 sks 65/35 poz 10% gel w/1/4 lbs. f.c. plus 400 lbs hulls.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:30PM Day: 11 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/4005 sks cement w/1/4 lbs. f.c. plus 300 lbs. hulls mixed in cement. Max 100 lbs. S.I. 300 lbs.

Pumped in 10 3/4 casing w/60 sks cement w/1/4 lb. f.c. and 50 lbs. hulls mixed in cement. Max 750 lbs. S.I. 400 lbs.

RECEIVED
JUL 24 1990
7-24-90
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:

INVOICED

If additional description is necessary, use BACK of this form.

I (did / did not) observe this plugging.

DATE: 7-30-90

INV. NO. 28812

7-11

Handwritten initials

Signed Dennis L. Hamel (TECHNICIAN)