

6 031390

7-17

(Handwritten mark)

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-02867-00 00

NE SE NW, SEC. 10, T 9 S, R 19 WXX

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Rostocil Well # C 6 S

Operator: Gore Oil Co.

County Rooks 123.53

Name & Address 202 S St. Francis

Well Total Depth 3801 feet

Wichita, Ks. 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well _____ Gas Well _____ Input Well (circled) SWD Well xx D&A _____

Other well as hereinafter indicated Docket D-02739

Plugging Contractor C and L Well Service License Number 1325

Address Plainville, Ks.

Company to plug at: Hour: PM Day: 17 Month: July Year: 19 90

Plugging proposal received from Lester Betts, David Gordon, Don Butcher

(company name) Gore Oil Co. (phone) _____

were: 8 5/8 set at 319 cwc w/175 sks. 5 1/2 set at 3456 w/150 sks. TOC 3100. 4 1/2 set at 3335-

3512 w/35 sks. Holes in pipe over large area. Drill out and washover to 1600. Run

tubing to 1600. Stage cement to surf. Order 150 sks common cement 250 sks 65/35 poz

8% gel 2%. Halliburton Cement Co. Roll/Darrell's Tank Service, C and L. Well

Service, Homco mud pump, swivel.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____

Operations Completed: Hour: 2:30PM Day: 17 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1640 with cir mix and pump thru tubing

50 sks common cement. Lay down tubing to 1130. Mix and pump 50 sks common cement.

Lay down tubing to 620 mix and pump 75 sks common cement. Circ. Lay down tubing.

Tie onto 5 1/2 sq w/150 sks 65/35 poz 8% gel 2% to max psi 500 lbs. Close in psi

500 lbs. Circ cement into cellar from 8 5/8. Plug complete.

Remarks: Anhy 1430 - '70.

AUG 17 1990
8-17-90

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE: 8-23-90

INV. NO. 29040

(Handwritten initials)

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow