

5-15
4-061074

15-163-03674-00-00

D-01,901

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 2-21-48
E2 SE SW /4 SEC. 12, 09 S, 19 W
660 feet from S section line
2970 feet from E section line

Operator license# 3258
Operator: Lansing Energy Corporation
Address: 107 North Market - Suite #115
Wichita, Kansas 67202

Lease Hilgers Well # 8
County: Rooks 123.63
Well total depth 3804 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1177 feet

Aband. oil well___, Gas well___, Input well___, SWD X, D & A___

Plugging contractor: Randy's Well Service License# -
Address: Plainville, Kansas 67663

Company to plug at: Hour: 8:00 A.M. Day: 15 Month: May Year: 1997

Plugging proposal received from: Rick Cornett

Company: Lansing Energy Corporation Phone: _____

Were: Order 150 sxs 60/40 posmix - 10% gel and hulls.
Run tubing to top of fish at 1000' and circulate cement.
3" cement lined tubing on packer plugged with debris and iron sulfide.

RECEIVED
MISAS ODP/COM
5/13/97
107 23 A 1:51


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30 P.M., Day: 15, Month: May, Year: 1997

Actual plugging report: 8 5/8" to 1186' w/475 sxs. 5 1/2" to 3544' w/200 sxs. Squeezed hole at 2418' w/400 sxs. Squeezed hole at 1828' w/450 sxs. Squeezed hole at 1668' w/800 sxs. Squeezed hole at 1666' w/150 sxs cement with cement to surface in annulus. Confirmed cement by visual inspection of braden head. Ran tubing and tagged fish. Circulated cement to surface with 85 sxs cement. Pulled tubing and tied onto casing. Pumped 15 sxs and pressured to 700#. Maintained and held pressure solid at 700#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD _____ Any plug: YES _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO X Dakota plug: YES X, NO _____
Plugged through TUBING X, CASING _____. Elevation: _____ 2069 _____ GL

I did [X] / did not [] observe the plugging.


DH (agent)
Form CP-2/3

INVOICED
DATE 5-27-97
INV. NO. 48181
5-15