

15-163-00597-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SE NW

SEC. 19 TWP. 9 RGE. 19 *w*

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Barber

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3594 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 154' circulated with cement. 5 1/2" at 3580' with
100 sax cement behind.

Filled with sand to 3570', set 4 sax cement with dump bailer,
pulled 2840' 5 1/2", mud to 154' set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC. 19 T. 9 R. 19
BOOK PAGE 58 LINE 27

RECEIVED
11/11/52
DIVISION

Edwin Perry
District Conservation Agent

Date 11-7-52