

15-163-00419-00-00

ye
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12/6/61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: NE NE SE Sec. 24 Twp. 9 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3616

I have this date completed supervision of plugging of:

Lease Name: Mayhew Well No. 1

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Lynch Pipe Pulling

Address: Great Bend, Kansas License No. 457

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 2 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 204' circulated with cement. 5 1/2" 3612' with 100 sax cement.

PB 3450', perforated ?

Filled with sand to 3300', set 5 sax cement with dump bailer - pulled 2980'

5 1/2" 50 550', circulated hole with heavy mud through 5 1/2" at 550' (19 sax Gel)

displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced

20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Lynch Co pump truck.

Signed: *Edwin Kelly*
Conservation Division Agent

Reviewed: *Harold Morris*
Field Supervisor

Remarks:

INVOICED
DATE 12/12/61
INV. NO. 4162-W