

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NE

SEC. 24 TWP. 9 RGE. 19W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-1 Lease Hilgers

Operator B & R Drg, INC Address Russell, Kans

Field _____ County Rooks

Total Depth 3641 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 290' circulated with cement - 5 1/2" at 3614' with
100 sax cement behind- perforated at 2509' sax squeezed with
75 sax cement at 2509'.

Filled with chat to 3600', set 4 sax cement with dump bailer,
pulled 1900' 5 1/2", filled with mud to 290', set rock and
15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
DISTRICT CONSERVATION AGENT
4/28/52
1952

Edwin Petty
District Conservation Agent

Date 4-24-52

PLUGGING
FILE SEC 24 TWP 9 RGE 19W
BOOK PAGE 12 LINE 14

CONSERVATION DIVISION
Wichita, Kansas