

15-163-03216-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1/14/62

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: ROOKS

Location: SE NE SE Sec. 24 Twp. 9 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3623'

I have this date completed supervision of plugging of:

Lease Name: Mayhew Well No. 3

Operator's Full Name: Morgenstern Spectre

Complete Address: Russell, Knasas

Plugging Contractor Ralph Lynch Pipe Pulling

Address: Great Bend, Kansas License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 10am Day 27 Month Dec Year 1961

The above well was plugged as follows:

TD-3623 8 5/8 set at 193' 5 1/2 set at 3417 1/2" Perfs at 3400'
Sand to 3300' and 5 sax cement. Shot 5 1/2 at 2815' and pulled same to
550' and circulated cement to the top with pump truck then displaced 20
sax cement thru 5 1/2" pipe, Pulled pipe to 180' and displaced 20 sax cement
thru 5 1/2, pulled pipe out of hole mud to 40' built rock bridge and 10 sax
cement.

Signed: Robert P. Leiker
Conservation Division Agent

Reviewed: Harold Morris
Field Supervisor

Remarks:

INVOICED
DATE 1/9/62
INV. NO. 4294-U