

15-163-19331-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6/15/64
JUN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co
Complete Address: 410 4th Natl Bk Bldg Wichita, Kansas
Lease Name Mayhew Well No. 1
Location W 1/2 NE SE Sec. 24 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3641
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Bert Self
Address: Hutchinson, Kans License No. 48
Operation Completed: Hour 5PM Day 10 Month 6 Year 64

The Above well, was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3641' with 100 sax cement - perf 3626'
Filled with sand to 3610', set 4 sax cement with dump bailer - pulled 1200' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eason Peety
Well Plugging Supervisor

DATE 6/15/64
INV. NO. 9298-W