

15-163-20821-00-00

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
6/19/78
JUN 19 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,821 (of this well)

Operator's Full Name Fleetwood Corporation

Complete Address Box 323, Olathe, Kansas

Lease Name Hilgers Well No. 1

Location N/2 SE NE Sec. 24 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3882'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor B & N Drlg.

Address Great Bend, Kansas License No. _____

Operation Completed: Hour 4:15 P Day 16 Month 6 Year 1978

The above well was plugged as follows:

RTD 3882' 8 5/8 csg. set 287' cwc 180 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob Massey
Well Plugging Supervisor

DATE 6-20-78

INV. NO. 7524-W