

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
8/30/74  
AUG 30 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company  
Complete Address P. O. Box 1201, Wichita, Kansas 67201  
Lease Name A. C. Stull Well No. 3  
Location C W/2 NE NW Sec. 17 Twp. 9 Rge. (E) (W) 19  
County Rooks Total Depth 3590'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Kelse Pipe Pulling  
Address Box 176, Chase, Kansas 67524 License No. 683  
Operation Completed: Hour 9:30 A Day 28 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3590' 10 3/4 csg set at 237' ewe 160 sk.

7" csg set at 3526' ew 150 sk.

7" csg FBTD 3470' & perf. (3331-3461)

Set 7" wood plug at 3000' -poured 20' sd -dumped 5 sk cmt W/dump bailer. (3000-2950)  
Cutoff & recovered 2391' of 7" csg.

Pumped down 10 3/4 csg with 20 sk gel & water -70 sk poz 6% -10 sk gel & water -  
released 10 3/4 plug & pumped 70 sk 70 sk poz 6% W/100 lbs hulls. PP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lio Z. Massey  
Well Plugging Supervisor

DATE 8/30/74

INV. NO. 9811-W