

15-163-20197-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/21/72
DEC 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company
Complete Address 217 N. Water Wichita, Kansas
Lease Name William L. Heroneme Well No. 2
Location NW NW NE Sec. 17 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3577'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering
Address Box 698 Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 4:30 P Day 20 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3577' 8 5/8 csg set at 205' cwc 175 sk.
5 1/2 csg set at 3572' cw 150 sk cmt.
5 1/2 csg PBTD 3532 with top perf. (3420')
Set 5 1/2 wood plug at 3400' -poured 25' sd -dumped 5 sk cmt W/dump bailer. (3340-3400)
Cutoff and recovered 2600' of 5 1/2 csg.
Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk gel
& water -released 8 5/8 plug and pumped 50 sk cmt. PP 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 12/22/72
INV. NO. 6755-W