

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 41-35
LOCATION SE SE SW
SEC. 18 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Marcotte
Operator Aylward Pro Co Address Wichita, Kans
Field _____ County Rooks
Total Depth 3595 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 158' circulated with cement - 5 1/2" at 3548 with
100 sax behind.

Lane Wells plugs to 3535' top perforations at 3370',
Filled with sand to 3360', set 4 sax cement with dump bailer,
shot pipe at 1975', circulated hole with 70 sax mud, pulled 1975'
5 1/2", set brock bridge at 158', with 15 sax cement, filled with
heavy mud to 40', set rock bridge and 10 sax cement to
bottom cellar

RECORDED
STATE CORPORATION
12/26/50
DEC 26 1950

PLUGGING
FILE SEC 18 T 9 R 19
BOOK PAGE 41 LINE 35

CONSERVATION DIVISION
Wichita, Kansas
[Signature]
District Conservation Agent
Date 12-22-50