

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
4/21/72  
APR 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kathol Petroleum, Inc.

Complete Address 900 Sutton Place Wichita, Kansas 67202

Lease Name Rempe Well No. 1

Location SW SW SE Sec. 18 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3579'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 12 N Day 20 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3579' 8 5/8 csg set at 207' cwc 200 sk. Cmt. Mat. 50-50 poz cmt 6% gel.

5 1/2 csg set at 3579' cw 200 sk cmt.

5 1/2 csg perf. (3260-3264)

Set 5 1/2 wood plug at 3200' -poured 30' sd -dumped 5 sk cmt W/dump bailer. (3135-3200)

Cutoff and recovered 775' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel & water W/500 lbs hulls, -70 sk cmt-

8 sk gel & water -released plug and pumped 50 sk cmt. PP 500 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey  
Well Plugging Supervisor

INVOICED  
DATE 4/21/72  
INV. NO. 5603-W