

15-163-20298-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

10/15/74  
OCT 15 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Kathol Petroleum Company

Complete Address 230 Sutton Place, Wichita, Kansas 67202

Lease Name Marcotte Well No. 2

Location NE NW SW Sec. 18 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3606'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No. 661

Operation Completed: Hour 12:15 P Day 12 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3606' 8 5/8 csg set at 209' cwc 150 sx.

5 1/2 csg set at 3526' cw 200 sx cem.

5 1/2 csg perf. (3292'-3369')

Filled 5 1/2 csg W/sd (3606'-3510') dumped 4 sx cem. W/dump bailer. (3510-3480)

Set 5 1/2 wood plug @ 3200' -poured 10' sd -dumped 4 sk cem W/dump bailer. (3200-3160)

Cutoff & recovered 890' Of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water -100 lbs hulls -70 sk 50-50 poz 6% -

10 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6% by " Allied ".

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 10/16/74  
INV. NO. 107-W