

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 33 TWP. 9 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Westhusin

Operator Musgrove Pet Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3563 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement - 5 1/2" at 3552' with
125 sax cement behind - Lane Wells plugs at 3470' - perforation s
at 3352'.

Filled with sand and chat to 3330', set 4 sax camet with dump
bailer - pulled 2632' 5 1/2" - filled with mud to 200', set rock
and 15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

PLUGGING
FILE SEC 33 9 R 17W
BOOK PAGE 78 LINE 32

2-11-53

District Conservation Agent
Date 2-10-53