

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
8-30-71
AUG 30 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lebem Drilling, Inc.

Complete Address Box 486 Great Bend, Kansas 67530

Lease Name Westhusin Well No. 1

Location C NW Sec. 33 Twp. 9 Rge. (E) (W) 17

County Reeks Total Depth 3578'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Pipe Pullers

Address Box 156 Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:15 A Day 27 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 3578' 8 5/8 csg set at 209' cwc 160 sk.

5 1/2 csg set at 3576' cw 150 sk cmt.

5 1/2 csg perf. 3233'

Filled 5 1/2 csg W/sd to 3560 - Dumped 3 sk cmt W/dump bailer.

Pushed 5 1/2 plug to 3200' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3150-3200)

Cutoff and recovered 2705' of 5 1/2 csg.

Pumped down 8 5/8 csg W/20 sk gel & water W/200 lbs. hulls. -70 sk reg poz 6% -

8 sk gel & water -release plug and pumped 50 sk reg poz 6% W/100 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messey
Well Plugging SupervisorDATE 8-31-71INV. NO. 4244-W