

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE SE

SEC. 11 TWP. 9 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Ruder

Operator Morganstern & Specter Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3492 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 157' circulated with cement - 5 1/2" at 3487' with 100 sax  
cement behind.

Filled with chat to 3470', set 4 sax cement with dump bailer - pulled  
2817' 5 1/2" - filled hole with heavy chunk mud to 370', set rock  
and 20 sax cement - heavy chunk mud to 35', set rock and 10 sax  
cement to bottom cellar.

District Conservation Agent

Date 4-20-57

PLUGGING  
FILE SEC. 11 T. 9 R. 19W  
BOOK PAGE 4 L. E. 11

RECEIVED  
STATE CORPORATION COMMISSION  
4/25/57