

15-163-21633-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita, Kansas 67202

Lease Name Ruder Well No. 2

Location SE SW SE Sec. 11 Twp. 9 Rge. 19 (E) XX (W) XX

County Rooks Total Depth 3475

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. tools

Address: License No.

Operation Completed: Hour 5:30 P Day 21 Month 11 Year 1968

The Above well was plugged as follows:

Total Depth 3475' 8 5/8 csg set at 219' cwc.

5 1/2 csg set at 3473' cw 100 sc.

5 1/2 csg squeezed at 1169' with 180 sc cmt. and 990' with 150 sc cmt.

No pipe. Recovered.

Displaced (thru tubing) 10 sc cement plug (3400-3475)

Circulated (thru tubing) 17 sc gel & Water (0-1140)

Displaced (thru tubing) 15 sc cement (1280-1140)
" " " " " (600-720)

Circulated (thru tubing) 35 sc cement (0-210)

Cutoff 5 1/2 csg and 8 5/8 csg and capped with 5 sc cement.
I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 11/26/68
INV. NO. 8870-W