

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20685 - 00 - 00 (of this well) Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11/13/78
NOV 13 1978

Operator's Full Name R. A. Comeau
Complete Address 311 South Jefferson, Plainville, Kansas 67663
Lease Name Ruder Well No. 1
Location SW SE SE Sec. 11 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3523'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 12 N Day 10 Month 11 Year 1978

The above well was plugged as follows:

Total Depth 3523' 8 5/8 csg set 200' cwc 150 sk.
5 1/2 csg set 3523' cw 150 sk cem. Perf. (3476'-3479')
Filled 5 1/2 csg W/sd (3523'-3450') dumped 4 sk cem. W/dump bailer. (3450'-3420')
Cutoff & recovered 2527' of 5 1/2 csg.
Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/3 sk hulls, followed with
70 sk 50-50 poz 6% -displaced with 10 sk gel & water -released plug & capped
with 50 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11-15-78
INV. NO. 8540-W

Signed: [Signature]
Well Plugging Supervisor