

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21, 693-00-00 R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name LIBERTY ENTERPRISES INC. H/c # 5562

Complete Address 308 WEST MILL PLAINVILLE, MO. 67663

Lease Name BALTHAZOR Well No. #1

Location NE-SW-SW Sec. 12 Twp. 9 Rge. 21 (East)(West)

County GRAHAM Total Depth 3736 ^{FT}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated H/c # 256

Plugging Contractor PIONEER DRILLING, INC (TOM ALM)

Address 308 WEST MILL, PLAINVILLE, MO. 67663 License No.

Operation Completed: Hour: 7:30 AM Day: 10th Month: OCT Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

(BY ALLIED)

8 5/8" - 209^{FT} SR. PVC. w/130ST 60/40 FORMIX-2% GEL-3% CA-CL.

ORDERED-200ST 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM-WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 3660^{FT} w/20ST CMT.

2ND PLUG @ 1650^{FT} w/20ST CMT.

3RD PLUG @ 870^{FT} w/100ST CMT.

4TH PLUG @ 240^{FT} w/40ST CMT.

5TH PLUG -> SOLID BRIDGE HULL'S-PLUG @ 40^{FT} w/10ST CMT. 10 IN RATHOLE (PIE)

Amount of Surface Casing: 209^{FT} CEMENTED BY ALLIED ON

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Martin Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED

STATE CORPORATION COMMISSION

10/19/82
OCT 19 1982

Signed: _____
Conservation Division Agent

INVOICED

DATE 11-16-82
INVOICE NO. 1595-W

CONSERVATION DIVISION
Wichita, Kansas