

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 111-32  
LOCATION SE SE SW  
SEC. 12 TWP. 9 RGE. 21

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Knipp

Operator Derby Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3687 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 3/8" at 320' circulated with cement - 4 1/2" at 3073' with  
150 sax cement behind.

Sand to 3060', set 3 sax cement with dump bailer - pulled  
approximately 2800' 4 1/2" - filled with mud to 315', set rock  
and 10 sax cement, mud to 33', set rock and 10 sax cement to  
bottom cellar.

**PLUGGING**  
FILE SEC 12 T 9 R 21W  
BOOK PAGE 111 LINE 32

8/8/53

Wichita, Kansas

*Edwin Perry*  
District Conservation Agent

Date 9-2-53