

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 9-30

LOCATION SE NW SW

SEC. 14 TWP. 9 RGE. 21

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 4 Lease Morel

Operator Continental Oil Co Address Pawco, Kans

Field County Graham

Total Depth 5771 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address

(Describe briefly the manner in which the well was plugged)

10 3/4" at 240' circulated with cement - 6" at 5700' with
300 sax cement behind.

Sand to 5700', set 5 sax cement with dump bailer, pulled

1000' 3", mud to 255', set rock and 20 sax cement, mud to

50', set rock and 10 sax cement to bottom cellar.

Received
2/12/54

Edward L. Terry
District Conservation Agent

Date 2-9-54

PLUGGING
FILE SEC. 14 T. 9 R. 21W
BOOK PAGE 9 LINE 30