


13-065-22432-00-00

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NE NW

SEC. 15 TWP. 9 RGE. 21

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 10 Lease Trexler

Operator Continental Oil Co Address Iyons, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3738 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 370' circulated with cement - 5 1/2" at 3678' with  
200 sax cement behind.

Filled with cement to 3662', pulled 2490' 5 1/2", filled hole with  
mud to 370', rock to 355', set 30 sax cement at 365', filled  
with mud to 30', set rock and 10 sax cement to bottom cellar.

STATE OF KANSAS

1/2/52  
JAN - 2 1952

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
District Conservation Agent

Date 12-30-51

**PLUGGING**  
FILE SEC 15 T 9 R 21  
BOOK PAGE 135 LINE 14