

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9/12/77  
SEP 12 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Sohio Petroleum Company

Complete Address Box 673, Russell, Kansas 67665

Lease Name Benson Well No. 5

Location SE NE SW Sec. 15 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3722'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:30 A Day 9 Month 9 Year 1977

The above well was plugged as follows:

RTD 3722' 8 5/8 csg set 1715' cwc 500 sk.

5 1/2 csg set 3716' cw 150 sk cem. with top perf. (3722'-3726') PBD 3630'

Filled 5 1/2 csg W/sd (3630'-3400') dumped 5 sk cem W/dump bailer. (3400'-3365')

Cutoff & recovered 2615' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg 50 sk 50-50 poz -displaced

with 36 bbl water & capped with 25 sk 50-50 poz & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 9-12-77  
INV. NO. 5822-W