

2

Form CP-3
Rev. 6-4-68

9/12/77
SEP 12 1977

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

(of this well)

ID # 10440

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Benson Well No. 2

Location C SE SW Sec. 15 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3873'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:15 P Day 9 Month 9 Year 1977

The above well was plugged as follows:

Total depth 3873' 8 5/8 csg set 267' cwc 110 sk.

5 1/2" csg set 3762' cw 100 sk cem. 4 1/2" liner set 3821-3723 & cem W/250 sk cem.

3 1/2" cem-lined tbg stuck in hole. pulled into at 315'.

Halliburton Cementing Co. mixed & pumped down 5 1/2" & 3 1/2" csg with 400 sk 50-50 poz

& shutin. FPP 1000 lbs. Down 8 5/8/5 1/2" annulus with 200 sk poz & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 9-12-77
INV. NO. 5230-4