

f

Form CP-3

Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9/12/77
SEP 12 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

D-14175

Operator's Full Name Sohio Petroleum Company

Complete Address Box 673, Russell, Kansas 67665

Lease Name Benson Well No. 4

Location NE SW SW Sec. 15 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3917'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 10 A Day 9 Month 9 Year 1977

The above well was plugged as follows:

Total Depth 3917' 10 3/4 csg set 241' cwc 250 sx.

5 1/2 csg set 3754' cw 150 sk cem. Squeezed at 1176' W/250 sk cem.

Top of 3 1/2" tbg fish 1538'

Filled 5 1/2 csg W/sd to 1400' -dumped 5 sk cem W/dump bailer. (1400'-1365')

Cutoff & recovered 450' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 10 3/4 csg with 125 sk 50-50 poz

& shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-12-77

INV. NO. 5820-W

Signed: Leo Messer
Well Plugging Supervisor