

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1972
6-29-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address P. O. Box #553, Russell, Kansas.
Lease Name Seefeld Well No. A-3
Location CSE-SW-NE Sec. 18 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3801'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Halliburton Services,
Address Box #339, Hays, Kansas. License No. _____
Operation Completed: Hour 2:30 PM Day 27 Month 6 Year 1972

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.
3788'--5 1/2" Production casing cemented on bottom with 175 Sx. DV Tool set @ 1773'
with 500 Sx. (Open hole completion). No attempt for recovery.
Squeezed 5 1/2" casing initially with 1 sack hulls and 30 Cu. Ft. cement from 3801 to
3750' then 28 sacks gel from 3750' to 950' and followed with 50 Cu. Ft. cement from
950 to 600' then 6 sacks gel from 600' to 25' and finally 10 Cu. Ft. cement from 25'
to bottom of cellar. Maximum pump-in pressure-2450#. Final shut-in pressure-2000#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/29/72

INV. NO. 5958-W