

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
6-21-71
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Seefeld Well No. A-7

Location CNW-NE-NE Sec. 18 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3784'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Halliburton Services,

Address Box #296, Hill City, Kansas. License No. _____

Operation Completed: Hour 1:00 PM Day 15 Month 6 Year 1971

The above well was plugged as follows:

280'--8 5/8" Surface casing, cement circulated with 275 Sx.
3780'--5 1/2" casing cemented on bottom with 175 Sx. 5 1/2" squeezed @ 1237' to surface
with 176 Sx. cement.

Squeezed 5 1/2" casing initially with 1 sack hulls and 20 Sx. cement from 3784' to 3650'
then 27 sacks gel from 3650' to 950' and followed with 44 Sx. cement from 950' to
600' then 3 sacks gel from 600' to 300' and finally 38 Sx. cement from 300' to 0'.

Maximum pump-in pressure- 1200#. Final shut-in pressure-700#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols
Well Plugging Supervisor

DATE 6/22/71

INV. NO. 5892-W