

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-20-71
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name Seefeld Well No. A-5
Location SE-NE-NE Sec. 18 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3784'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #405, Chase, Kansas. License No. 624
Operation Completed: Hour 6:00 PM Day 15 Month 12 Year 1972

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.
3779'--5 1/2" Production casing cemented on bottom with 175 Sx. No plug back nor perfor-
ations indicated.

Sanded well back to 3760' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(314') and squeezed well initially with 5 sacks hulls and 18 gel and followed with
110 Cu. Ft. cement from 925' to 600' then 8 sacks gel from 600' to 280' and followed
with 30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally
10 Cu. Ft. cement from 40' to bottom of cellar. (Mudding and cementing by Halliburton).
Maximum pump-in pressure-350#. Final shut-in pressure-175#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dickols
Well Plugging Supervisor

DATE 1-6-72
INV. NO. 4839-W