

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3/3/64
MAR 3 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name American Petrofina Company of Texas.

Complete Address: Box # 209, Russell, Kansas.

Lease Name Ford Well No. 1

Location SE-SE-SE Sec. 29 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3915

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company.

Address: Box # 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 27 Month 2 Year 1963

The Above well was plugged as follows:

255'--8 5/8" Surface pipe, cement circulated.

3911'--5 1/2" Production casing cemented with 75 Sx.

Sanded well back to 3900' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing to 628' and pumped in 9 Sx. heavy gel mud, well would not

circulate. Pulled 5 1/2" to 535' and circulated hole with 17 Sx. heavy gel

mud and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 240' and displaced

20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 3/3/64

INV. NO. 8732W