

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3/1/72
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name Karst Well No. 1

Location NE-SW-NW Sec. 29 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3878'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 11:30 AM Day 26 Month 2 Year 1972

The above well was plugged as follows:

234'--8 5/8" Surface casing, cement circulated with 160 Sx.
3873'--5 1/2" Production casing cemented on bottom with 150 Sx. No Plug back nor perfor-
ations indicated.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1600') and squeezed well initially with 5 sacks hulls and 16 sacks gel and followed
with 110 Cu. Ft. cement from 975' to 650' then 10 sacks gel from 650' to 250' and
followed with 30 Eu. Ft. cement from 250' to 175' then 4 sacks gel from 175' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure
500#. Final shut-in pressure-200#. (Mudding and cementing operations by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/1/72
INV. NO. 5163-W

Signed: A. L. D'Almeida
Well Plugging Supervisor