

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
9/23/69
SEP 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company, Incorporated,
Complete Address 1425 Wichita Plaza Building, Wichita, Kansas.
Lease Name Karst Well No. 2
Location SE-NW-NW Sec. 29 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3900'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 1:30 PM Day 19 Month 9 Year 1969

The above well was plugged as follows:

235'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 650'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/23/69
INV. NO. 526-W

Signed: N. L. Nichol
Well Plugging Supervisor