

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
7/31/63
JUL 31 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shallow Water Refining Company,

Complete Address: 542 Petroleum Building, Wichita, Kansas.

Lease Name Harrold Well No. 2

Location CN $\frac{1}{2}$ -N $\frac{1}{2}$ -SW Sec. 29 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3890

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Hammonds Well Service,

Address: Box #276, Plainville, Kansas License No.

Operation Completed: Hour 10:30AM Day 27 Month 7 Year 1963

The Above well was plugged as follows:

181'--8 5/8" Surface pipe, cement circulated. 3885'--5 1/2" cemented with ??.
Dakota sands squeezed to surface.
Sanded well back to 3850' and set 5 Sx cement with dump bailer. Found top
of fluid @1100', set 20' bridge and 6 Sx cement. Set plug @ 230' with 15'
bridge on top and 20 Sx cement. Set plug @ 30' and 5 Sx cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/30/63
INV. NO. 7500-W

Signed: M. L. Nichols
Well Plugging Supervisor