

24
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1-3-72
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation,

Complete Address Box #1934, Oklahoma City, Oklahoma.

Lease Name Balthazor Well No. 5

Location CS/2-SW-NE Sec. 23 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3792'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 2:00 PM Day 28 Month 12 Year 1971

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated.
3778'--5 5/8" Production casing cemented on bottom with 150 Sx. No plug back nor per-
forations indicated. Ran tools in hole, unable to get below 1870'. Pushed plug to
1870', sanded back to 1850' and set 5 Sx. cement with dump bailer. Pulled 5 5/8" casing
635' and attempted to squeeze well normally. Squeezed initially with 4 sacks hulls
and 17 sacks gel, gained circulation around surface casing with gel @ 250#. Shut
well down, called service unit, attempted to wash out gel and hulls to spot cement.
Ran 2" tubing to 90' where it stopped, tried to circulate with clear water and gel
"hydraulicized" out of surface, size of casing. Mixed "Heavy Cement" and circulated
cement from 90' to bottom of cellar with 50 Sx. (Mudding and cementing by Sun).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-10-72

INV. NO. 4892-4

Signed: *M. L. D. [Signature]*
Well Plugging Supervisor