

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 68-35  
LOCATION NW NW SW  
SEC. 23 TWP. 9 RGE. 21

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. R-1 Lease Lewis "B"

Operator Cities Service Oil Address Box 553 Russell, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3843 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 175' circulated with cement - 5 1/2" 3838' with 100 sax  
cement behind.

Filled with sand to 3830', set 4 sax cement with dump bailer,  
started 600' 5 1/2" - circulated hole with heavy mud (Gel) at 600',  
displaced 35 sax cement through 5 1/2" at 600', heavy mud to 160',  
displaced 25 sax cement through 5 1/2" at 160', heavy mud to 35', set  
rock and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

John Hannah

By *E. L. Hannah*

District Conservation Agent

Date 12-21-57

12-27-57  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FILE SEC 23 T. 9 R. 21  
BOOK PAGE 68 LINE 35