

69

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Lewis Well No. B-2

Location SE-SW-SW Sec. 23 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3810'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Halliburton Services,

Address: Hays, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 10:30AM Day 11 Month 10 Year 1968

The Above well was plugged as follows:

283'--8 5/8" Surface casing, cement circulated with 150 Sx.

3808'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back. 5 1/2" squeezed thru leak @ 1329' with 119 Sx. common cement.

Checked sand fill-up in well with measuring line and found 5 1/2" filled up to 3790'.

Squeezed 5 1/2" with 20 sacks gel with 5 sacks hulls in initial gel and followed with

75 Sx. 50-50 Poz-Mix with 6% gel. Maximum pump-in pressure--700#. Final shut-in

pressure--100#.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

OCT 16 1968

CONSERVATION DIVISION

Wichita, Kansas

Signed: [Signature]

Well Plugging Supervisor

INVOICED

DATE 10-16-68

INV. NO. 8647-W