

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 38-3
LOCATION SW NW NW
SEC. 23 TWP. 9 RGE. 21

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A-1 Lease Putnam
Operator Continental Oil Co Address Geneseo, Kans
Field _____ County Graham
Total Depth 3804 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 203' circulated with cement.
9 5/8" at 1518' cement to 400'. 7" 3794' with 70 sax cement
behind.
Filled with chat to 3785', set 5 sax cement with dumpbailer,
pulled 2300', 7" casing, pulled 400' 9 5/8", filled with
mud to ~~400'~~ 300', set rock and 20 sax cement, mud to ~~300'~~
35' set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 23 T 9 R 21
BOOK PAGE 21 LINE 3

STATE CORPORATION COMMISSION
SEP 18 1952
9-18-52
CONSERVATION DIVISION
Wichita, Kansas

Edmund Perry
District Conservation Agent
Date 9-10-52