

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1962  
8-21-62  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name John Casebeer

Complete Address: Box 151 Mc Pherson, Kansas

Lease Name Putnam Well No. A-6

Location SE SE NW Sec. 23 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3809

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: R & D Casing Pulling

Address: Hutchinson, Kans License No. 236

Operation Completed: Hour 2PM Day 16 Month 8 Year 62

The Above well was plugged as follows:

~~10 3/4" 378' circulated with cement - 6" 3766' with 300 sax cement PB 3790' Perforated 3497'~~

~~Set plug at 3490', sand to 3470', set 5 sax cement with dump bailer, pulled 1500' 6" to 500', circulated hole with heavy mud through 6" at 500', displaced 20 sax cement through 6" at 500', heavy mud to 180', displaced 20 sax cement through 6" at 180', heavy mud to 30', set bridge and 10 sax cement to bottom cellar.~~

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8/22/62

INV. NO. 5565-W

Signed: Edouard Lette  
Well Plugging Supervisor