

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE NE SW SE

SEC. 8 TWP. 9 RGE. 19 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Zigler Zeigler

*507 Mayo Bldg.  
Tulsa, Okla.*

Operator Wentworth & Sons Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3577 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3570' with  
60 sax cement behind. Lane Wells plugs to 3525' top perforation  
3509'.

Filled with chat to 3500', set 4 sax cement with dump bailer.  
pulled 3085' 5 1/2", filled hole with mud to 185', set bridge and  
15 sax cement, filled with mud to 35', set rock and 10 sax cement  
to bottom cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
4-26-51  
APR 26 1951

*[Signature]*  
CONSERVATION DIVISION  
Wichita, Kansas  
District Conservation Agent

Date 4-25-51

**PLUGGING**  
FILE SEC 8 T 9 R 19 W  
BOOK PAGE 77 LINE 44

