

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

DEC 4 1959
12-4-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks
Location: SE NE SE Sec. 8 Twp. 9 Rge. 19 (E) (W) _____
Name of Field: _____ Total Depth: 3354

I have this date completed supervision of plugging of:

Lease Name: Ziegler Well No. 1

Operator's Full Name: Allen Fender

Complete Address: Box 302 Russell, Kans

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No ☒

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 20 Month 11 Year 59

The above well was plugged as follows:

8 5/8" 1478' circulated with cement - 5 1/2" 3341' 100 sax cement. PB to 3369',
perforated 3296'

Filled with sand to 3285', set 4 sax cement with dump bailer, pulled 2825' 5 1/2"
to 550', circulated hole with heavy mud through 5 1/2" (30 sax Gel), displaced
20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced 20 sax cement
through 5 1/2" at 170', heavy mud to 30', filled with cement 30' to 0".

Mudding and cementing by Globe Cementing Co.

Signed: Edwin Petty
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED

DATE 1/13/60

INV. NO. 459-W