

STATE CORPORATION COMMISSION

11-16-59

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks

Location: NE SE SE Sec. 8 Twp. 9 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3535

I have this date completed supervision of plugging of:

Lease Name: Zeigler Well No. 2

Operator's Full Name: Allen Fender

Complete Address: Box 302 Russell, Kans

Plugging Contractor: Barnes & Sons Pipe Pulling

Address: Russell, Kans License No. 9

Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No ☒

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 10 Month 11 Year 59

The above well was plugged as follows:

8 5/8" at 150' circulated with cement - 5 1/2" 3535' with 100 sax cement.

Baker plugs to 3370', perforated 3310'.

Filled with sand to 3300', set 4 sax cement with dunn bailer, pulled 2800' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced 20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Eason Petty
Conservation Division AgentReviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED

DATE 1/13/60

INV. NO. 450-a