

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 113-8 County: Rooks

Location: SW NW NE Sec. 32 Twp. 9 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3756

I have this date completed supervision of plugging of:

Lease Name: Stucky Well No. A-1

Operator's Full Name: Grant Oil Co

Complete Address: 518 W K H Bldg Wichita, Kans

Plugging Contractor: H. D. Arnett Casing Pulling

Address: Hoisington, Kans License No. 265

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Other well as hereafter indicated: Old well wash down

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 11 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 160' circulated with cement - 5 1/2" 3734' with 100 sax cement
behind - P. B. to 3510' perforated 3356'.

Filled with chat to 3330', set 4 sax cement with dump bailer, pulled
1680' 5 1/2" to 550', circulated hole with heavy mud at 550' through 5 1/2".
40 sax gel) displaced 20 sax cement through 5 1/2" at 550', heavy mud to
150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 40',
set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edson Leety*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING	
FILE	SEC <u>32</u> T <u>9</u> R <u>18</u> W
BOOK	PAGE <u>113</u> LINE <u>8</u>

RECEIVED
STATE CORPORATION COMMISSION
7/19/58
JUL 19 1958